

SETTING UP OF RAJIV GANDHI INSTITUTE OF PETROLEUM TECHNOLOGY AT SIVASAGAR, ASSAM

RAJIV GANDHI INSTITUTE OF PETROLEUM TECHNOLOGY (RGIPT)
SIVASAGAR, ASSAM

(BIDDING DOCUMENT NO. A-059/T-40/10-11/SJ/03)

BIDDING DOCUMENT FOR SITE GRADING WORKS FOR RAJIV GANDHI INSTITUTE OF PETROLEUM TECHNOLOGY AT SIVASAGAR, ASSAM

PART –II (PRICE PART)

PROJECT MANAGERS
ENGINEERS INDIA LIMITED
1, BHIKAJI CAMA PLACE
R.K. PURAM, RING ROAD
NEW DELHI-110066

ARCHITECTS
ARCHITECT HAFEEZ CONTRACTOR
29 BANK STREET
MUMBAI

Prepared & Issued by:



TENDER FEE: RS. 1,000.00 (Non-refundable)

INDEX

S.NO.	DESCRIPTION	NO.OF SHEETS
1	Cover page	1
2	Index	1
3	Preamble to Schedule of Rates	1
4	Schedule of Rates	1

PREAMBLE TO SCHEDULE OF RATES

- 1 The Schedule of Rates shall be read with all other sections of this Bidding Document and price shall be as per scope of work, scope of supply and all taxes, duties including service tax, all statutory and other requirements (if any), obligations etc., as mentioned in various sections / specifications/ S.O.R. of the bidding document.
- 2 The CONTRACTOR is deemed to have studied the drawings, specifications and details of works to be done within the Time Schedule and should have acquainted himself of the conditions prevailing at site.
- 3 The quantity shown against the various items are only approximate and may vary to any extent individually subject to provisions of Bidding Document..
- 4 OWNER/ EIL reserves the right to interpolate or extrapolate the rates for any new item of work not covered in Schedule of Price from the similar items already available in schedule of rates. Where it is not possible, rate shall be derived as per provision of the terms and conditions of the bidding document. All the works shall be measured upon completion and paid for at the rate quoted and accepted in the "Schedule of Rates". In case any activity though specifically not covered in schedule of rates descriptions but the same is covered under scope of work/ scope of supply/ specification/ drawings etc. no extra claim on this account shall be entertained, since Schedule of Rates is to be read in conjunction with all other documents forming part of the Contract.
- 5 The rates shall include for all incidental and contingent expenses and risks of every kind necessary to complete work in accordance with the Contract.
- 6 SOR
 - i) While quoting and filling the rate in this Schedule of Rates, Bidder shall take into consideration complete scope of work/item description as mentioned in Schedule of Rates for the relevant item and in above paras. The rate quoted in Schedule of Rate shall be deemed to include all activities of work mentioned in item description of Schedule of Rates.
7. OWNER/ EIL reserve the right to cancel/ delete/ curtail any item or group of work if necessary. Such a step shall not be construed as reason for changing the rates.
8. The borrow area for sourcing earth will be in the scope of the contractor. RGIPT will not arrange borrow earth.
- 9 Contractor responsibility will also include obtaining the required permissions and adhering to the environmental rules.

STAMP & SIGNATURE OF BIDDER

NAME OF WORK:		SITE GRADING WORKS FOR RAJIV GANDHI INSTITUTE OF PETROLEUM TECHNOLOGY AT SIVASAGAR, ASSAM					
NAME OF PROJECT:		SETTING UP OF RAJIV GANDHI INSTITUTE OF PETROLEUM TECHNOLOGY AT SIVASAGAR, ASSAM					
BIDDING DOC. NO.:		A-059/T-40/10-11/SJ/03					
		<u>SCHEDULE OF RATES</u>					
SL. NO.	ITEM NO.	ITEM DESCRIPTIONS	UNIT	QUANTITY	RATE		AMOUNT (RS)
					(IN FIG.) (RS)	(IN WORDS)	
1	1	SITE GRADING					
		Earthwork in filling with borrow earth for all heights and depths for site grading or at any other place as directed to proper levels, slopes, grades and camber with selected earth obtained from approved borrow areas within a lead of 12Km from site limit including excavation of earth at borrow areas, clearing and stripping at borrow areas (if necessary), loading, unloading, transportation etc. clearing and stripping as per specifications, uprooting of vegetation, roots and disposal of the shrubs, bushes, roots etc., breaking clods, spreading in layers not exceeding 30 cm loose thickness , watering, ramming and compacting with road roller to give at least 90% of max. laboratory dry density as per IS:2720 Part VII, providing and operating POL and operator charges of necessary road rollers and other equipment, providing testing apparatus and testing the degree of consolidation, dressing and levelling, etc. complete, including disposal of all unserviceable materials if any, to dumping areas anywhere out side site boundary limits and ultimate disposal of wood generated including royalties etc. complete as per drawings, specifications and directions of Engineer-In-Charge. (Borrow areas shall be arranged by Contractor and the Contractor shall bear all expenses towards royalties , right of way etc. complete and rate quoted shall also include all royalties , right of way etc) Complete .	CUM	25,000			
		TOTAL PRICE					