



Ref. RGIPT/JAIS/IED/QE/2025-26/03

Date: 26.11.2025

To,

.....

.....

.....

GSTIN:

Sub: Quotation enquiry for the misc. electrical wiring work in the new academic building at RGIPT, Jais Campus.

Dear Sir,

We request you to submit your competitive rates (quotation) for misc. electrical wiring work to provide power supply to the AC units and computer tables in the new academic building at RGIPT, Jais campus as per the attached as **Annexure-1**.

Terms & Conditions:

- The quoted rate should be inclusive of **GST & Freight charges**. Agency is requested to only fill the required data in the prescribed format only as per the attachment Annexure-1, no extra terms and condition should be mentioned by the Agency. If he does so, then the quotation of that agency will be summarily rejected.
- The quoted rate shall be valid for a period of 90 days from the last date of submission of quotation.
- GST number should be mentioned in the quotation.
- The total time for completion of work will be 30 days. The date of commencement shall be reckoned from the date of acceptance of Work Order.
- No advance payment will be made. The agency should inspect the site before quoting the rate.
- The work will be carried out as per technical specification & satisfaction of Engineer-in-Charge..
- In case of any damage and delay in completion of work, liquidated damages (LD) at the rate of 0.5% of the work order value per week of delay or part thereof, subject to a maximum of 10% of the work order value shall be recovered from the agency/contractor bills.
- The quotation should be sent to us duly **Signed and Stamped** only in **Sealed Envelope** and Super scribed as **Ref. No. RGIPT/JAIS/IED/QE/2025-26/03, Quotation for misc. electrical wiring work in the new academic building at RGIPT, Jais Campus** by registered post or by hand to the office of The Chairman, Institute Electricity Department, Rajiv Gandhi Institute of Petroleum Technology Jais, Mukhetiya More, Harbanshganj , Tiloi , Amethi, UP – 229304.

- i) The quotation should be submitted within 10 days from the date of quotation enquiry i.e., the quotation should be received on or before 05.12.2025 by 04:00 PM. Quotation received after the due date, for whatever reason, will not be considered for evaluation.
- j) The order will be awarded to the Agency/Contractor, whose rate will be lowest in terms of the grand total.
- k) The Institute reserves the right to accept/reject all or any part of the offer without assigning any reason thereof.

Amal K.
26/11/24

Chairman-Institute Electricity Department

Annexure-1					
Miscellaneous electrical wiring work in the New Academic Building at RGIPT.					
Sl. No.	Description	Unit	Qty.	Unit Price (Rs.)	Total Price (Rs.)
1.0	Distribution Board				
1.1	Supplying and fixing of following ways surface/ recess mounting, vertical type, 415 V, TPN MCB distribution board of sheet steel, dust protected, duly powder painted, inclusive of 200 A tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCBs (but without MCBs and incomer) as required.				
1.1.1	4 way (4 + 12), Double door	Nos.	4		
1.2	Incoming: Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required.				
1.2.1	125 A, 16 kA, TPMCCB	Nos.	4		
1.3	Outgoing				
1.3.1	63 amps 4P MCB, 10 kA C curve	Nos.	4		
1.3.2	32 amps Single Pole MCB, 10 kA C curve	Nos.	24		
2.0	Cable Connections:				
2.1	Supplying of Al. Armoured XLPE Cable				
2.1.1	4 Core X 35 Sq.mm. Al. Armoured XLPE Cable	Mtrs.	110		
2.2	Laying of Al. Armoured XLPE Cable				
2.2.1	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE Al. Armoured power cable of 1.1 KV grade and size 4 Core X 35 Sq.mm. on wall surface as required.	Mtrs.	110		
2.3	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				
2.3.1	4 Core X 35 Sq.mm. Al. Armoured XLPE Cable	Nos.	8		
3.0	Circuit Wiring				
3.1	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.				
3.1.1	2 X 6 sq. mm + 1 X 6 sq. mm earth wire	Mtrs.	70		
3.1.2	2 X 4 sq. mm + 1 X 4 sq. mm earth wire	Mtrs.	180		
3.1.3	2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	Mtrs.	35		
4.0	Switches and Sockets				
4.1	Supply and fixing of 6/16 Amp, 2 switch + 2 socket with PVC Box complete in all respect	Nos.	20		
4.2	Supply and fixing of 6/16 Amp, 1 switch + 1 socket with PVC Box complete in all respect	Nos.	10		
A	Total Amount (in Rs.)				
B	GST Charges (in Rs.)				
C	Total Amount inclusive of GST (in Rs.) (Sl. No.A + Sl. No.B)				